Name of Work:- PACKAGE No-03 Providing grill fencing and other developmental works at Sardara vallabai patel park, Sangolli rayanna park, Ambedkar park and Providing Gym & Children Play Equipments to Various Parks in Yelahanka Assembly Constituency Under Amrutha Nagarothana Grants

Calculation Sheet for Dismentling Fencing

Sl No	Discription	Length of existing available Chain link fencing in Mtrs	Details	Weightin Kg/mt/Sqm	Quantity in Kgs	Rate /Kg	Amount in Rs.
1	Fencing Pole (65x65x6)mm Equal angle		Angle Length inMtrs				
	Sangolirayanna Park	182.93	365.86	5.80	2121.99	22.00	46683.74
	Krishna Devaraya Park East s	67.18	134.36	5.80	779.29	22.00	17144.34
2	Fencing Pipe 14 guage (Aclass 40mm Pipe)		Nos of Pipes				
	Sangolirayanna Park	182.93	2	3.20	1170.75	22.00	25756.54
	Krishna Devaraya Park	67.18	2	3.20	429.95	22.00	9458.94
3	Fencing Mesh		Height of Mesh				
	Sangolirayanna Park	182.93	1.50	4.57	1253.99	22.00	27587.67
	Krishna Devaraya Park	67.18	1.50	4.57	460.52	22.00	10131.42
	Total in Rs.						136762.65

Assistant Engineer
Project Division Yelahanka

Asst. Executive Engineer
Project Division Yelahanka

Asst. Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore - 92

Scanned by TapScanner